

#### To the New Owner:

### Congratulations!


You are the owner of a state-of-the-art Gas Fireplace by FPI FIREPLACE PRODUCTS INTERNATIONALLTD. The P36 has been designed to provide you with all the warmth and charm of a wood fireplace at the flick of a switch. The model P36 has been approved by Warnock Hersey for both safety and efficiency. As it also bears our own mark, it promises to provide you with economy, comfort and security for many trouble free years to follow. Please take a moment now to acquaint yourself with these instructions and the many features of your FPI Fireplace.

### INFORMATION FOR MOBILE/MANUFACTURED HOMES AFTER FIRST SALE

This FPI product has been tested and listed by Warnock Hersey as a Vented Gas Fireplace Heater to the following standards: CAN/CGA-2.17-M91, and ANSI Z21.88b-2003/CSA 2.33b-2003.

This Direct Vent System Appliance must be installed in accordance with the manufacturer's installation instructions and the Manufactured Home Construction and Safety Standard, Title 24 CFR, Part 3280, or the current Standard of Fire Safety Criteria for Manufactured Home Installations, Sites, and Communities ANSI/NFPA 501A, and with CAN/CSA Z240-MH Mobile Home Standard in Canada.

This appliance installation must comply with the manufacturer's installation instructions and local codes, if any. In the absence of local codes follow the current National Fuel Gas Code, ANSI Z223.1 and the current National Electrical Code ANSI/NFPA 70 in the U.S.A., and the current CAN/CGA B149 Gas Installation Code and the current Canadian Electrical Code CSA C22.1 in Canada.



## TABLE OF CONTENTS

#### SAFETY LABEL

Cofoty Lobal	E
Salety Laber	 O

#### INSTALLATION

Before You Start    7      General Safety Information    7      Installation Checklist    7
Locating Your Gas Fireplace
HeatWave Duct System (optional)8 Heat Release Kit (optional)8
Clearances9Regency Clearances10Arch Door Clearances10Hampton Clearances10Palace Series Clearances10
Regency Mantel Clearances11Hampton Mantel Clearances12Palace Series Mantel Clearances14
Mantel Leg Clearances 15
Framing and Finishing
Unit Assembly Prior to Installation Top Standoff Assembly
Venting Introduction
Venting 21 Direct Vent System (Flex) 21 Rigid Pipe Venting Components List 22 Rigid Pipe Venting Systems
Horizontal or Vertical Terminations 23

Venting Arrangements	0.4
Horizontal Terminations	
Vertical Terminations	21
Vertical Terminations - Co-Linear Flex System	
Venting Arrangements - Vertical Terminations	
Venting - Dura-Vent Horizontal Installations	
Venting - Dura-Vent Vertical Termination	
Venting - Installation for Direct Vent System (Flex)	
System Data	
High Elevation	
Gas Line Installation	
Pilot Adjustment	
Gas Pipe Pressure Test	
SIT Valve Description	
Conversion from Natural Gas to Propane	35
Brick Panels (optional)	36
G	
Log Set Installation	36
Standard Flush Door	39
Remote Control (optional)	
Remote Wall Switch (optional)	
Wall Thermostat (optional)	40
Wiring Diagram	
Alternative Wiring for Wall Switch	42

#### **OPERATING INSTRUCTIONS**

Fan Installation (optional)	43
Operating Instructions	43
Lighting Procedure	44
Shutdown Procedure	44
First Fire	44
Aeration Adjustment	44
Normal Operating Sounds	44
Lighting Plate Instructions	45

**NOTE:** All installation instructions apply to Regency, Hampton & Palace Series unless otherwise specified.

## TABLE OF CONTENTS


#### MAINTENANCE

Maintenance Instructions General Vent Maintenance	
Gold-Plated or Brass Louvers Gold Plated or Brass Trim	
Log Replacement Thermopile/Thermocouple	
Glass Gasket Door Glass Flush Glass Replacement Bay Glass Replacement	46 46
Removing Valve Installing Valve	47 47

#### HAMPTON CAST FACEPLATE OPTION

Hampton	Cast	Faceplate	57
Hampton	Cast	Grills	58

# PALACE SERIES OPTIONS The Kensington Front 60 The Westminster Front 61 The Balmoral Front 62



#### REGENCY FLUSH & BAY DOOR OPTIONS

Flush Trim Louvers - Flush	-
Double Screen Door	49
Bay Door Bay Trim Bay Louvers	50
Finishing Trim	51
Full Screen Front Arch Screen Door	52 54
Cothespire	

## SAFETY LABEL

This is a copy of the label that accompanies each P36 Zero Clearance Direct Vent Gas Fireplace. We have printed a copy of the contents here for your review. The safety label is located on the front inside base of the unit, visible when the bottom louver is open.

**NOTE:** FPI units are constantly being improved. Check the label on the unit and if there is a difference, the label on the unit is the correct one.

DO NOT REMOVE THIS LABEL / NE PAS ENLEVER CETTE ÉTIQUETTE Top, sides, bottom and rear of unit 908-792d Horizontal Top 2" (51mm) Horizontal Side 1-1/2" (38mm) Horizontal Bottom 1-1/2" (38mm) 1-1/4" (32mm) Mantel Clearances from Top: (A) Min. 7" (177mm) Side Wall Clearance from Side Facing B) 6" with Flush or Bay Front B) 8" with Barcelona Trim Alcove approved for Bay & Flush Louvers. Alcove Clearances: Max Depth 36" (914mm) Min. Weight 72" (1229mm), Min. Height 72" (1229mm), Minimum Vent Clearances Serial No./ No de serie FPI Fireplace Products International Ltd. Minimum Clearances to Combustibles /Degagement Minimum De Materiaux Combustibles 0" Clearance to combustibles from: Vertical Vent Delta, BC, Canada lj lj Wa used with the Bay Glass option Louvers" MUST be 213 DOOR SEAL: Please Made in Canada/Fabrique au Car m (See Instruction Manual for Detailed Instructions) Ч Ч 213 check that the door properly sealed ч ₹ 32" Ceiling 4 4 4 "Bay I Duplicate S/N 44 Copy of Safety Decal for P36-NG3 (Natural Gas) The Ч Ч Ч IIeN APPAREIL FONCTIONNANT AU NATURAL GAS 555 CONCU POUR ETRE POELE: Modéle P36-NG3 follow the National Fuel Gas Code, ANSI Z223 1/NFPA 54, or Natural Gas and Propane Installations Codes, CSA B149.1. For Manufactured Home Installation: This Direct Vent System Appliance must be installed in accordance with the manufacturer's installation instructions and Manufactured Home Construction and Safety Standard Title 24 CFR, Part 3280, or the current Fan (Part # 432-917) Optional Bay Window (Part #780-931) Option: HeatWave Kit # 946-556 Standard for Fire Safety Criteria for Manufactured Home Installations, Sites, and Communities ANSI/NFPA 501A, and with CAN/CSA Z240 MH Mobile Home Standard in Canada. Pression à la tubulure d'échappement élevée Pression à la tubulure d'échappement basse VENTING: This appliance must be installed in accordance with local codes, if any; if none, Certified for/Certifiée pour: CANADA and U.S.A. Tested to: CAN/CGA-2.17-M91, ANSI Z21.88b-2003/CSA 2.33b-2003 Report No. 476-3059100 (June 2004) MAY BE INSTALLED IN MANUFACTURED (MOBILE) HOMES AFTER FIRST SALE. Ч ĥ NOT FOR USE WITH SOLID FUELS. ц Ц Pression d'allimentation minimum Débit Calorifique maximum selon Débit Calorifique minimum selon h łı Y Grandeur de l'injecteur ĥ ններներներներ Listed: VENTED GAS FIREPLACE HEATER This vented gas fireplace heater is not for use with air filters. l'altitude (4.54 kW) D (8.79 kW) D (0-1372 m) I (0.95 kPa) (0.27 kPa) (1.25 kPa) Electrical supply 115VAC, 1.13 A, 60Hz. Btu/h Btu/h ft/pi DMS WC ХC NC 15,500 E 30,000 E 0-4500 f NATURAL GAS: Model P36-NG3 1.1" # 37 3.8 Minimum supply pressure 5" Manifold pressure high Manifold pressure low ŝ Maximum input Minimum input 5454544 Orifice size Altitude

Ce

For the State of Massachusetts, installation

and repair must be done by a plumber or gasfitter licensed in the Commonwealth of

For the State of Massachusetts, flexible


connectors shall not exceed 36 inches in

For the State of Massachusetts, the appliances individual manual shut-off must be a

Massachusetts.

t-handle type valve.

length.



## IMPORTANT: SAVE THESE INSTRUCTIONS

The P36-NG or P36-LP Direct Vent Fireplace must be installed in accordance with these instructions. Carefully read all the instructions in this manual first. Consult the "authority having jurisdiction" to determine the need for a permit prior to starting the installation. It is the responsibility of the installer to ensure this fireplace is installed in compliance with manufacturer's instructions and all applicable codes.

## **BEFORE YOU START**

Safe installation and operation of this appliance requires common sense, however, we are required by the Canadian Safety Standards and ANSI Standards to make you aware of the following:

INSTALLATION AND REPAIR SHOULD BE DONE BY A QUALIFIED SERVICE PERSON. THE APPLIANCE SHOULD BE INSPECTED BEFORE USE AND AT LEAST ANNUALLY BY A PROFESSION-ALSERVICE PERSON. MORE FREQUENT CLEANING MAY BE REQUIRED DUE TO EXCESSIVE LINT FROM CARPETING, BEDDING MATERIAL, ETC. IT IS IMPER-ATIVE THAT CONTROL COMPART-MENTS, BURNERS AND CIRCULATING AIR PASSAGEWAYS OF THE APPLI-ANCE BE KEPT CLEAN.

DUE TO HIGH TEMPERATURES, THE APPLIANCE SHOULD BELOCATED OUT OF TRAFFIC AND AWAY FROM FURNI-TURE AND DRAPERIES.

WARNING: FAILURE TO INSTALL THIS APPLIANCE CORRECTLY WILL VOID YOUR WARRANTY AND MAY CAUSE A SERIOUS HOUSE FIRE.

CHILDREN AND ADULTS SHOULD BE ALERTED TO THE HAZARDS OF HIGH SURFACETEMPERATURES, ESPECIAL-LY THE FIREPLACE GLASS, AND SHOULD STAY AWAY TO AVOID BURNS OR CLOTHING IGNITION.

YOUNG CHILDREN SHOULD BE CARE-FULLY SUPERVISED WHEN THEY ARE IN THE SAME ROOM AS THE APPLI-ANCE.

#### CLOTHING OR OTHER FLAMMABLE MATERIAL SHOULD NOT BE PLACED ON OR NEAR THE APPLIANCE.

## GENERAL SAFETY INFORMATION

- The appliance installation must conform with local codes or, in the absence of local codes, with the current Canadian or National Gas Codes, CAN1-B149 or ANSI Z223.1 Installation Codes.
- 2) The appliance when installed, must be electrically grounded in accordance with local codes, or in the absence of local codes with the current National Electrical Code, ANSI/NFPA 70 or CSA C22.1 Canadian Electrical Code.
- See general construction and assembly instructions. The appliance and vent should be enclosed.
- 4) This appliance must be connected to the specified vent and termination cap to the outside of the building envelope. Never vent to another room or inside a building. Make sure that the vent is fitted as per Venting instructions.
- Inspect the venting system annually for blockage and any signs of deterioration.
- 6) Venting terminals shall not be recessed into a wall or siding.
- 7) Any safety glass removed for servicing must be replaced prior to operating the appliance.
- To prevent injury, do not allow anyone who is unfamiliar with the operation to use the fireplace.
- 9) Wear gloves and safety glasses for protection while doing required maintenance.
- **10)** Be aware of electrical wiring locations in walls and ceilings when cutting holes for termination.
- 11) Under no circumstances should this appliance be modified. Parts that have to be removed for servicing should be replaced prior to operating this appliance.
- 12) Installation and any repairs to this appliance should be done by a qualified service person. A professional service person should be called to inspect this appliance annually. Make it a practice to have all of your gas appliances checked annually.

- 13) Do not slam shut or strike the glass door.
- 14) Under no circumstances should any solid fuels (wood, paper, cardboard, coal, etc.) be used in this appliance.
- **15)** The appliance area must be kept clear and free of combustible materials, (gases and other flammable vapours and liquids).

Emissions from burning wood or gas could contain chemicals known to the State of California to cause cancer, birth defects or other reproductive harm.

## INSTALLATION CHECKLIST

- 1) Locate appliance
  - a) Room location, page 8.
  - b) Clearances to Combustibles, pages 9 -14.
  - c) Mantle Clearances, pages 15.
  - d) Framing & Finishing Requirements, page 16.
  - e) Venting Requirements, pages 21-30.
- 2) Assemble Top Standoffs and Top Facing Support and Side Nailing Strips, page 19. (NOTE: must be done before installing unit into fireplace.)
- 3) Install vent, pages 31-33.
- 4) Make gas and electrical connections. Test the pilot. Must be as per diagram on page 34.
- 5) Install brick panels (optional), page 36.
- 6) Install log set where indicated, page 36.
- 7) Install standard Flush Door, page 39.
- 8) Install Optional Regency Flush or Bay Fronts. pages 55.
- 9) Install Optional Hampton Cast Faceplate, page 56-59.
- 10) Install Optional Palace Series Fronts, pages 59-65.
- 11) Install Optional Arch Door, pages 54-55.
- 12) Install Optional Wall Switch, Remote Control, or Wall Thermostat, page 40.
  12) Install Optional Factoria (2016)
- 13) Install Optional Fan, page 43.

14) Final check.

Before leaving this unit with the customer, the installer must ensure that the appliance is firing correctly and **operation fully explained to customer**.


#### This includes:

- Clocking the appliance to ensure the correct firing rate (rate noted on label 30,000 Btu/h) after burning appliance for 15 minutes.
- 2) If required, adjusting the primary air to ensure that the flame does not carbon. First allow the unit to burn for 15-20 min. to stabilize.

CAUTION: Any alteration to the product that causes sooting or carboning that results in damage is not the responsibility of the manufacturer.

# LOCATING YOUR GAS FIREPLACE

- When selecting a location for your fireplace, ensure that the clearances outlined on this page are met.
- 2) Provide adequate clearances for servicing.
- 3) The appliance must be installed on a flat, solid, continuous surface (e.g. wood, metal, concrete). This may be the floor, or raised up on a platform to enhance its visual impact. If the appliance is going to be installed on carpeting, combustible linoleum tile or other combustible material other than wood flooring, the appliance must be installed on a metal or wood panel extending the full width and depth of the appliance.
- 4) The P36 Direct Vent Gas Fireplace can be installed in a recessed position or framed out into the room as in A, B, C, D. See Diagram 1.



- A) Flat on Wall
- B) Flat on Wall Corner
- C) Recessed into Wall/Alcove
- D) Corner
- 5) This appliance is Listed for bedroom installations when used with a Listed Millivolt Thermostat. Some areas may have further requirements, check local codes before installation.
- The P36 Direct Vent Gas Fireplace is approved for alcove installations, which meet the clearances listed on this page.
- 7) We recommend that you plan your installation on paper using exact measurements for clearances and floor protection before actually installing this appliance. Have a qualified inspector, dealer, or installer review your plans before installation.
- Note: For vent terminations see page 20.

### MANUFACTURED MOBILE HOME ADDITIONAL REQUIREMENTS

- Ensure that structural members are not cut or weakened during installation.
- 2) Ensure proper grounding using the #8 ground lug provided. See page 41.



## DUCT SYSTEM OPTION KIT #946-556

The *HeatWave* Air Duct Kit increases the effectiveness of your fireplace by dispersing warm air from the fireplace to remote locations in the same room or other rooms in your home.

Up to two kits may be installed on the fireplace. **Please Note:** Only 1 HeatWave kit may be operated at one time. This includes the internal blower option as well.



The **HeatWave** Duct Kit has different clearance and framing requirements, check the **HeatWave** manual for details.

## OPTIONAL HEAT RELEASE KIT #946-570

The Heat Release Kit expels warm air from the fireplace to the outside of the building, allowing the fireplace to be operated with less heat entering the room. The kit may be used on either the left or right side.

## **CLEARANCES**


The clearances listed below are Minimum distances unless otherwise stated:


A major cause of chimney related fires is failure to maintain required clearances (air space) to combustible materials. It is of the greatest importance that this fireplace and vent system be installed only in accordance with these instructions.

IMPORTANT: See page 17 for framing note on Barcelona Trim and Palace Series Fronts. See page 18 for framing note on Arch Door.

Clearance to Combustibles from: Back 0" (0mm) Side 0" (0mm) Floor 0" (0mm) NOTE: The minimum floor clearance must be maintained from the top surface of the carpeting, tile, etc. Minimum Clearance from Top of Unit to: Ceiling from top of unit. 32" (1016mm) Side Wall Clearances: 6"\* **Bay or Flush Front** (152mm) Barcelona Trim 6"\* (152mm) **Cast Faceplate** 6"\* (152mm) 6"\* **Kensington Front** (152mm) **Balmoral & Westminster Front** 6"\* (152mm) \* Measured from Surround or Front. See page 15 for dimensions. Horizontal Vent Clearances: Тор 2' (51mm) Side 1-1/2" (38mm) 1-1/2" (38mm) Bottom Vertical Vent Clearances 1-1/4" (32mm) Alcove Clearances\*\*: Max. Depth 36" (914mm) Min. Width 48" 1219mm) 1829mm) Min. Height 72" \*\*Approved for one sidewall installation only when using Barcelona Trim. WARNING: Fire hazard is an extreme risk if these clearances are not adhered to. Barcelona & Double Screen Door Installations The HeatWave Duct Kit and the Heat Heat Wave To install the combination of the Barcelona front and screen doors. Release Kit have different clearance you must use non-combustible mantel in conjunction with the and framing requirements, check the already required framing specs for the Barcelona front. HeatWave and Heat Release manual Steel studs and non-combustible material on the facing must be Heat Release Kit for details. adhered to.

#### **REGENCY CLEARANCES**






## REGENCY SERIES COMBUSTIBLE MANTEL CLEARANCES

Because of the extreme heat this fireplace emits, the mantel clearances are critical. Combustible mantel clearances from top of unit are shown in the diagram below.

Note: A non-combustible mantel may be installed at a lower height if the framing is made of metal studs covered with a noncombustible board.




These drawings are to scale at 1:6 (one inch = 6 inches) Mantel can be installed anywhere in shaded area or higher using the above scale.

Note: Ensure the paint that is used on the mantel and the facing is "heat resistant" or the paint may discolour.

## HAMPTON COMBUSTIBLE MANTEL CLEARANCES

Because of the extreme heat this fireplace emits, the mantel clearances are critical. Combustible mantel clearances from top of unit are shown in the diagram below.

Note: A non-combustible mantel may be installed at a lower height if the framing is made of metal studs covered with a noncombustible board.




These drawings are to scale at 1:6 (one inch = 6 inches) Mantel can be installed anywhere in shaded area or higher using the above scale.

Note: Ensure the paint that is used on the mantel and the facing is "heat resistant" or the paint may discolour.

## PALACE SERIES COMBUSTIBLE MANTEL CLEARANCES

Because of the extreme heat this fireplace emits, the mantel clearances are critical. Combustible mantel clearances from top of unit are shown in the diagram below.


Note: A non-combustible mantel may be installed at a lower height if the framing is made of metal studs covered with a noncombustible board.



These drawings are to scale at 1:6 (one inch = 6 inches)

Mantel can be installed anywhere in shaded area or higher using the above scale.

Note: Ensure the paint that is used on the mantel and the facing is "heat resistant" or the paint may discolour.




## **REGENCY MANTEL LEG CLEARANCES**

## PALACE SERIES MANTEL LEG CLEARANCES


Combustible mantel leg clearances as per diagram:

Kensington Front Width: 42-5/8" Balmoral Front Width: 40-5/8" Westminster Front Width: 40-5/8"



## FRAMING AND FINISHING


 Determine the total thickness of facing material (e.g. drywall plus ceramic tiles) to allow the finished surface to be flush with the front of the unit. Total facing thickness can vary from 1/2" (13mm) to 1-1/4" (32mm) thick.




Install Side Nailing Strips, Top Facing Support, and Top Standoffs before unit is slipped into position. See page 16 for assembly details.

2) Frame in the enclosure for the unit with framing material. The framed opening is 36-1/4" high x 36-1/4" wide x 12-3/4" deep (921mm high x 921mm wide x 324mm deep).

Note: Header must be installed vertically. If Header is installed horizontally, it must be steel.






NOTE: See next page for important Barcelona and Palace Series framing note.

D	ns	Dimensio	Framing	
L	D	С	В	А
	46"*	12-3/4"	36-1/4"	36-1/4"
	1168mm*	324mm	921mm	921mm

\* 'D' is Minimum height to combustible materials including the Minimum 2" (51mm) Top clearance to the Horizontal Vent.

- 3) For exterior walls, insulate the enclosure to the same degree as the rest of the house, apply vapour barrier and drywall, as per local installation codes. (Do not insulate the fireplace itself.)
- The top of the unit must not be closer than 32" (813mm) to the ceiling.




- ote: 40-1/2" (1029mm) is the minimum height for both flex termination or Simpson Dura-Vent venting.
- Note: The unit does not have to be completely enclosed in a chase. The clearance on top of the unit is 0" to the standoffs so combustible building materials can be laid directly on top of the standoffs. You must maintain 1-1/2" (38mm) clearance from the vent to combustible materials for flex (1-1/4" for Simpson Dura-Vent).
- Use steel studs for framing where the 1-1/2" (38mm) clearance from the vent to combustible material cannot be maintained, e.g. front top header.

### **BARCELONA & PALACE SERIES FRAMING NOTE**

When installing the optional Barcelona Front or Palace Series, a non-combustible material 12" (305mm) above the unit and 6" (153mm) on each side must be used. See diagram 1.


The Barcelona Front and Palace Series also requires steel stud framing above and on each side of the unit. See diagram 1.



### ARCH DOOR SERIES FRAMING NOTE

When installing the optional Arch Door Series, a non-combustible material 12" (305mm) above the unit and 6" (153mm) on each side must be used. See diagram 2.

The Arch Door Series also requires steel stud framing above and on each side of the unit. See diagram 2.




## UNIT ASSEMBLY PRIOR TO INSTALLATION

The Top Facing Support, the Side Nailing Strips and the 2 Top Standoffs must be correctly positioned and attached to the top before unit is slipped into position.

#### **Top Standoff Assembly**

The top standoffs are shipped in a flat position and must be folded into shape and attached.

- 1) Remove the standoffs from the fireplace top.
- Take each standoff and bend into the correct shape. Bend up at the bend lines until the screw holes in the standoff and the prepunched screw holes on the fireplace top line up.
- Attach the standoff securely to the top with 2 screws per standoff (on opposite corners).



#### Top Facing Support and Side Nailing Strips

Determine the total thickness of facing material (e.g. drywall plus ceramic tiles) to allow the finished surface to be flush with the front of the unit. Total facing thickness can vary from 1/2" (13mm) to 1-1/4" (32mm) thick.


The Top Facing Support & Side Nailing Strips can be mounted in 3 different positions depending on the thickness of the facing material.

Screw	Facing Material		
Position	Depth		
A	1/2"	/ 13mm	
B	7/8"	/ 22mm	
C*	1-1/4"	/ 32mm	

- \* For "C" screw position the top facing support is reversed.
- Mount Top Facing Support using the 3 supplied screws into the three pre-punched screw holes on the top front of the unit. Use hole positions A, B, or C depending on your facing depth.

#### "C" Screw Position:

For a facing material depth of 1-1/4" (32mm), the top facing support must be reversed.




2) Use the same screw hole position for the Side Nailing Strips as was used for the Top Facing Support. Attach each side nailing strip using 3 screws.

## VENTING INTRODUCTION

The P36 uses the "balanced flue" technology Co Axial system. The inner liner vents products of combustion to the outside while the outer liner draws outside combustion air into the combustion chamber thereby eliminating the need to use heated room air for combustion and losing warm room air up the chimney.

#### Note: These flue pipes must not be connected to any other appliance.

The gas appliance and vent system must be vented directly to the outside of the building, and never be attached to a chimney serving a separate solid fuel or gas burning appliance. Each direct vent gas appliance must use it's own separate vent system. Common vent systems are prohibited.




EXTERIOR VENT TERMINATION LOCATIONS

## VENTING

#### FPI Direct Vent System (Flex) Horizontal **Terminations Only**

These venting systems, in combination with the P36 Direct Vent Gas Fireplace, have been tested and listed as a direct vent heater system by Warnock Hersey. The location of the termination cap must conform to the requirements in the Vent Terminal Locations diagram on page 20

FPI Direct Vent (Flex) System Termination Kit (Part # 946-515) includes all the parts needed to install the P36 with a maximum run of 4 feet.



Notes:

- 1) Liner sections should be continuous without any joints or seams.
- 2) Only Flex pipe purchased from FPI may be used for Flex installations.
- 3) If you are installing the P36 into a FPI Cabinet Mantel Kit, use the minimum horizontal vent height (centre-line of 40-1/2"). Remember to include the mantel base (3" in height) in your calculations and to maintain the 2" clearance to the underside of the mantel top.

### **RIGID PIPE VENTING COMPONENTS LIST**

All Simpson Dura-Vent components are available directly from FPI.

Description	Simpson Dura-Vent Direct VentGS <sup>R</sup>	Selkirk Direct-Temp™	Amerivent <sup>R</sup> Direct Vent
6" Pipe Longth Colyanized	908	4DT-6	N/A
6" Pipe Length, Galvanized 6" Pipe Length, Black	908 908B	4DT-6B	N/A N/A
7 Pipe Length, Galvanized	908B N/A	4D1-66 N/A	4D7
7 Pipe Length, Black	N/A N/A	N/A N/A	4D7 4D7B
	907	4DT-9	AD7B N/A
9" Pipe Length, Galvanized			
9" Pipe Length, Black	907B	4DT-9B	N/A
12" Pipe Length, Galvanized	906	4DT-12	4D12
12" Pipe Length, Black	906B	4DT-12B	4D12B
18" Pipe Length, Galvanized	N/A	4DT-18	N/A
18" Pipe Length, Black	N/A	4DT-18B	N/A
24" Pipe Length, Galvanized	904	4DT-24	4D2
24" Pipe Length, Black	904B	4DT-24B	4D2B
36" Pipe Length, Galvanized	903	4DT-36	4D3
36" Pipe Length, Black	903B	4DT-36B	4D3B
48" Pipe Length, Galvanized	902	4DT-48	4D4
48" Pipe Length, Black	902B	4DT-48B	4D4B
Adjustable Length, 11"-14", Galv.	911	4DT-AJ	N/A
Adjustable Length, 11"-14", Black	911B	4DT-AJB	N/A
Adjustable Length, 17"-24", Black	917B	N/A	N/A
Adjustable Length, 7" Galvinized	N/A	N/A	4D7A
Adjustable Length, 7" Black	N/A	N/A	4D7AB
Adjustable Length, 12" Galvinized	N/A	N/A	4D12A
Adjustable Length, 12" Black	N/A	N/A	4D12AB
45° Elbow, Galvinized	945	4DT-EL45	4D45L
45° Elbow, Black	945B	4DT-EL45B	4D45LB
45° Elbow, Swivel, Galvinized	945G	N/A	N/A
45° Elbow, Swivel, Black	945BG	N/A	N/A
90° Elbow, Galvinized	990	4DT-EL90S	4D90LS
	990 990B		4D90LS 4D90LBS
90° Elbow, Black	990B 990G	4DT-EL90SB	
90° Elbow, Swivel, Galvinized 90° Elbow, Swivel, Black	990G 990BG	N/A N/A	N/A N/A
Ceiling Support	949 - n/a from FPI	4DT-CS	4DFSP
Cathedral Support Box	941	4DT-CSS	4DRSB
Wall Support/Band	988	4DT-WS/B	4DWS
Offset Support	989 - n/a from FPI	4DT-OS	N/A
Wall Thimble, Black	942	4DT-WT	4DWT
Wall Thimble, Black Wall Thimble Support Box/Ceiling Support	940	N/A	N/A
Firestop Spacer	963	4DT-FS	4DFSP
Trim Plate, Black	N/A	4DT-TP	4DFPB
Brass Trim for Wall Thimble/Ceiling Support	3951	N/A	N/A
Attic Insulation Shield 12"	N/A	N/A	4DAIS12
Attic Insulation Shield - Cold Climates 36"	N/A	N/A	4DAIS36
Basic Horizontal Termination Kit (A)	970	4DT-HKA	4DHTK2
Horizontal Termination Kit (B)	971	4DT-HKB	4DHTK1
Vertical Termination Kit	978	4DT-VKC	4DVTK
High Wind Vertical Cap	991	N/A	N/A
High Wind Horizontal Cap	985	N/A	N/A
Horizontal Square Termination Cap	984	4DT-HHC	4DHC
Verical Termination Cap	980	4DT-HVC	4DVC
Storm Collar	953	4DT-SC	4DSC
Adjustable Flashing, 0/12-6/12	943	4DT-AF6	4DF
Adjustable Flashing, 6/12-12/12	943S	4DT-AF12	4DF12
Vinyl Siding Standoff	950	4DT-V9	NI/A
Vinyl Siding Standoff Vinyl Siding Shield Plate	950 N/A	4DT-VS 4DT-VSP	N/A N/A
Snorkel Termination 14"	982	4DT-ST14	4D12S
Snorkel Termination 36"	981	4DT-ST36	4D36S
946-506/P Vent Guard (Optional)	946-20	5 Vinvl Siding Shield fo	or Riser Vent Terminal
510-994 Rigid Pipe Adaptor (Must use			I) - Riser Vent Terminal
	<b>o i o</b> ,		
640-994 U37 Rigid Pipe Adaptor	946-52	3/P AstroCap Horizontal	Cap
640-530/P Riser Vent Terminal	946-20		

## RIGID PIPE VENTING SYSTEMS Horizontal or Vertical Terminations


The minimum components required for a basic horizontal termination are:

- 1 Horizontal Termination Cap
- 1 90° Elbow
- 1 Rigid Pipe Adaptor
- 1 Wall Thimble
- 1 Length of pipe to suit wall thickness (see chart)

Wall thickness is measured from the back standoffs to the inside mounting surface of termination cap. For siding other than vinyl furring strips may be used, instead of the vinyl siding standoff, to create a level surface to mount the vent terminal. The Terminal must not be recessed into siding. Measure the wall thickness including furring strips.

If a Vinyl Siding Standoff is required (it must be used with vinyl siding), measure to outside surface of wall without siding and add 2 inches.

Flat Wall Installation				
Wall Thickness	Vent Length			
(inches)	Required (inches)			
4" - 5-1/2"	6"			
7" - 8-1/2"	9"			
10" - 11-1/2"	12"			
9" - 14-1/2"	11" - 14-5/8" Adj. Pipe			
15" - 23-1/2"	17" - 24" Adj. Pipe			
Corner	Installation			
Wall Thickness	Vent Length			
(inches)	Required (inches)			
3-1/4" - 6-3/4"	11" - 14-5/8" Adj. Pipe			
7-3/4" - 16-1/4"	17" - 24" Adj. Pipe			
7-1/4" - 8-3/4"	6" + 12"			
	9" + 9"			
4-1/4" - 5-3/4"	6" + 9"			




The FPI AstroCap<sup>™</sup> and FPI Riser Vent terminal is certified for installations using FPI venting systems as well as Simpson Dura-Vent®, Direct Vent GS, American Metal Products, Ameri Vent Direct vent and Selkirk Direct-Temp. FPI<sup>™</sup>, and FPI AstroCap<sup>™</sup> are the proprietary trademarks of FPI Fireplace Products International Ltd. Dura-Vent® and Direct Vent GS are registered and/or proprietary trademarks of Simpson Dura-Vent Co. Inc.

### RIGID PIPE VENTING ARRANGEMENTS - HORIZONTAL TERMINATIONS FPI DIRECT VENT SYSTEM (FLEX) (Propane & Natural Gas)

The diagram shows all allowable combinations of vertical runs with horizontal terminations, <u>using one 90° elbow</u> (two 45° elbows equal one 90° elbow).

Note: Must use optional rigid pipe adaptor (Part # 510-994) when using Rigid Pipe venting systems.




- Maintain clearances to combustibles.
- · Horizontal vent must be supported every 3 feet.
- · Firestops are required at each floor level and whenever passing through a wall.


NOTE: If you are installing the P36 into a FPI Cabinet Mantel Kit, use the minimum horizontal vent height (centre-line of 40-1/2"). Remember to include the mantel base (3" in height) in your calculations and to maintain the 2" clearance with rigid pipe and flex systems to the underside of the mantel top.

#### Horizontal Venting with Two (2) 90° Elbows

One 90° elbow = Two 45° elbows.




### Horizontal Venting with Three (3) 90° Elbows




#### Vertical Venting with Two (2) 90° Elbows

#### One $90^{\circ}$ elbow = Two $45^{\circ}$ elbows.

Option	V	Н	V + V1			
A)	0' Min.	2'Max.	1' Min.	With these options, max.		
B)	1' Min.	4'Max.	2' Min.	total pipe length is 30 feet with min. of 6 feet total		
C)	2' Min.	5'Max.	3' Min.	vertical and max. 8 feet		
D)	3' Min.	6'Max.	4' Min.	total horizontal.		
E)	4' Min.	7'Max.	5' Min.			
F)	5' Min.	8'Max.	6' Min.	Please note min. 1 foot between 90° elbows is		
Lengths do not include elbow indicated required.						
For additional vertical venting with 2 x 90° elbows, refer to next page.						



#### Vertical Venting with Three (3) 90° Elbows




One 90° elbow = Two 45° elbows.

Option	V	H + H1	V + V1	
A)	0' Min.	2'Max.	2' Min.	With these options, max.
B)	1' Min.	2'Max.	3' Min.	total pipe length is 30 feet
C)	2' Min.	3' Max.	4' Min.	with min. of 10 feet total
D)	3' Min.	4'Max.	6' Min.	vertical and max. 8 feet total horizontal.
E)	4' Min.	5' Max.	7' Min.	total norizontal.
F)	5' Min.	6' Max.	8' Min.	Please note min. 1 foot
G)	6' Min.	7' Max.	9' Min.	between 90° elbows is
H)	7' Min.	8' Max.	10' Min.	required.
Lengths do not include elbow indicated			*	

## RIGID PIPE VENTING ARRANGEMENTS - VERTICAL TERMINATIONS (Propane & Natural Gas)

The shaded area in the diagram shows all allowable combinations of straight vertical and offset to vertical terminations, using two 90° elbow, with **Rigid Pipe** vent systems for Propane and Natural Gas.



The P36 is approved for a 40 ft. straight vertical, with **rigid pipe** vent systems for Propane and Natural Gas, as per the diagram 1. Horizontal (Feet) 0 The shaded area in the diagram 1 shows all allowable combinations of straight 40 vertical and offset to vertical terminations with rigid pipe vent systems for Propane and Natural Gas. Maximum two 45° elbows allowed. 38 -Vent must be supported at offsets. • Firestops are required at each floor level and whenever passing • through a wall. 36 Maintain clearances to combustibles. . 34 32 30 28 24 ۲ Maximum: 40 ft. 22 Vertical Height (Feet) 20 -7.0' 18 -Y 16 2013 14 12 10 8 6in. Minimum: 10 ft. 6 4 2 -11


0

Diagram 1

### VERTICAL TERMINATION WITH CO-LINEAR FLEX SYSTEM

Masonry chimneys may take various contours which the flexible liner will accommodate. However, **keep the flexible liner as straight as possible**, avoid unnecessary bending.

The Air Intake pipe must be attached to the inlet air collar of the termination cap.




THE APPLIANCE MUST NOT BE

CONNECTED TO A CHIMNEY FLUE

SERVING A SEPARATE SOLID FUEL BURNING APPLIANCE.





The shaded area in the diagrams show the allowable vertical terminations.

Riser Vent

Termination


## HORIZONTAL INSTALLATIONS

# Install the vent system according to the manufacturer's instructions included with the components.

- Set the unit in its desired location. Check to determine if wall studs or roof rafters are in the way when the venting system is attached. If this is the case, you may want to adjust the location of the unit. Rough in the gas preferably on the right side of the unit and the electrical (junction block is on the left side) on the left.
- 2) Direct Vent pipe and fittings are designed with special twist-lock connections to connect the venting system to the appliance flue outlet. A twist-lock appliance adaptor is an available option that must be used in conjunction with the Simpson Dura-Vent Direct Vent GS system.
- 3) Put a bead of silicone inside the outer section of the adapter and a bead of Stove Mate on the inner collar. Slip the adapter over the existing inner and outer flue collar and fasten to the outer collar only with the 3 supplied screws (drilling pilot holes will make this easier). Level the fireplace and fasten it to the framing using nails or screws through the nailing strips.
- Assemble the desired combination of pipe and elbows to the appliance adaptor and twist-lock for a solid connection.


#### Note:

a) Twist-lock procedure: Four indentations, located on the female ends of pipes and fittings, are designed to slide straight onto the male ends of adjacent pipes and fittings, by orienting the four pipe indentations so they match and slide in to the four entry slots on the male ends, Diagram 1. Push the pipe sections completely together, then twist-lock one section clockwise approximately onequarter turn, until the two sections are fully locked. The female locking lugs will not be visible from the outside, on the Black Pipe or fittings. They may be located by examining the inside of the female ends.



Note: Apply sealant "Mill-Pac" to inner pipe and high temperature silicone sealant to outer pipe on every twist-lock joint.


- b) Horizontal runs of vent must be supported every three feet. Wall straps are available for this purpose.
- 5) Mark the wall for a 10" x 10" square hole. The center of the square hole should line up with the centerline of the horizontal pipe. Cut and frame the 10 inch square hole in the exterior wall where the vent will be terminated. If the wall being penetrated is constructed of non-combustible material, i.e. masonry block or concrete, a 7"(178mm) dia. (7-1/2"(191mm) dia. for flex) hole is acceptable.



- a) The horizontal run of vent must be level, or have a 1/4 inch rise for every 1 foot of run towards the termination. Never allow the vent to run downward. This could cause high temperatures and may present the possibility of a fire.
- b) The location of the horizontal vent termination on an exterior wall must meet all local and national building codes, and must not be blocked or obstructed. For External Vent Terminal Locations, see diagram on page 19.

#### c) Snorkel Terminations:

For installations requiring a vertical rise on the exterior of the building, 14-inch and 36-inch tall Snorkel Terminations are available, as well as the standard Riser Dura-Vent Vent. Follow Snorkel the same installation proce-Min. 12"\* , dures as (305mm) used for Π standard Horizontal Termination. NEV-ER install the snorkel upside down. Ω Diagram 3




If the Snorkel Termination must be installed

below grade, i.e. basement application, proper drainage must be provided to prevent water from entering the Snorkel Termination. Refer to Diagram 4. Do not attempt to enclose the Snorkel within the wall, or any other type of enclosure.

Dura-Vent Snorkel UIV UV UV Window Well Adequate drainage Gravel Diagram 4

- NOTE: For Snorkel terminations in ABOVE grade installations, follow national or local code requirements.
- 6) The arrow on the vent cap should be pointing up. Insure that the 1-1/2" clearances to combustible materials are maintained (Diagram 4). Install the termination cap.


The four wood screws provided should be replaced with appropriate fasteners for



#### Diagram 5

stucco, brick, concrete, or other types of sidings.

- Note: If installing termination on a siding covered wall, a vinyl siding standoff or furring strips must be used to ensure that the termination is not recessed into the siding.
- Before connecting the horizontal run of vent pipe to the vent termination, slide the Wall Thimble over the vent pipe.
- 8) Slide the appliance and vent assembly towards the wall carefully inserting the vent pipe into the vent cap assembly. It is important that the vent pipe extends into the vent cap sufficient distance so as to result in a minimum pipe overlap of 1-1/4 inches. Secure the connection between the vent pipe and the vent cap by attaching the two sheet metal strips extending from the vent cap assembly into the outer wall of the vent pipe. Use the two sheet metal screws provided to connect the strips to the pipe section. See Diagram 6.



## VERTICAL TERMINATION

- Maintain the 1-1/4" clearances

   (air spaces) to combustibles
   when passing through ceilings,
   walls, roofs, enclosures, attic
   rafter, or other nearby combustible surfaces. Do not pack
   air spaces with insulation.
   Check for the maximum vertical
   rise of the venting system and
   the maximum horizontal offset
   limitations.
- Set the gas appliance in its desired location. Drop a plumb bob down from the ceiling to the position of the appliance flue exit, and mark the location


where the vent will penetrate the ceiling. Drill a small hole at his point. Next, drop a plumb bob from the roof to the hole previously drilled in the ceiling, and mark the spot where the vent will penetrate the roof. Determine if ceiling joists, roof

11 11

Diagram 1

rafters or otherframing will obstruct the venting system. You may wish plumber's to relocate the tape appliance or to connected to wall strap offset, as shown in Diawall 45 gram 2 to avoid strap Elbows cutting load bearing members. Firestop Female Locking Lugs Spacer Diagram 2 Mill-Pac ■Silicone Male Locking

- Note: Apply sealant "Mill-Pac" to inner pipe and high temperature silicone sealant to outer pipe on every twist-lock joint.
- 3) A Firestop spacer must be installed in the floor or ceiling of every level. To install the Firestop spacer in a flat ceiling or wall, cut a 10 inch square hole. Frame the hole as shown in Diagram 3 and install the firestop.



- Assemble the desired lengths of pipe and elbows. Ensure that all pipes and elbow connections are in the fully twist-locked position and sealed.
- 5) Cut a hole in the roof centered on the small drilled hole placed in the roof in Step 2. The hole should be of sufficient size to meet the minimum requirements for clearance to combustibles of 1-1/2". Slip the flashing under the shingles (shingles should overlap half the flashing) as per Diagram 4.




Diagram 4: The upper half of the flashing is installed under the roofing material and not nailed down until the chimney is installed. This allows for small adjustments.

6) Continue to assemble pipe lengths.

Note: If an offset is necessary in the attic to avoid obstructions, it is important to support the vent pipe every 3 feet, to avoid excessive stress on the elbows, and possible separation. Wall straps are available for this purpose (Diagram 2).

Galvanized pipe is desirable above the roofline due to its higher corrosion resistance. Continue to add pipe sections through the flashing until the height of the vent cap meets the minimum height requirements specified in Diagram 5 or local codes. Note that for steep




Roof Pitch	Minimum Vent Height		
	Feet	Meters	
flat to 7/12	2	0.61	
over 7/12 to 8/12	2	0.61	
over 8/12 to 9/12	2	0.61	
over 9/12 to 10/12	2.5	0.76	
over 10/12 to 11/12	3.25	0.99	
over 11/12 to 12/12	4	1.22	
over 12/12 to 14/12	5	1.52	
over 14/12 to 16/12	6	1.83	
over 16/12 to 18/12	7	2.13	
over 18/12 to 20/12	7.5	2.29	
over 20/12 to 21/12	8	2.44	

roof pitches, the vertical height must be increased. A poor draft, or down drafting can result from high wind conditions near big trees or adjoining roof lines, in these cases, increasing the vent height may solve the problem.

- 7) Ensure vent is vertical and secure the base of the flashing to the roof with roofing rails, slide storm collar over the pipe section and seal with a mastic.
- 8) Install the vertical termination cap by twistlocking it.
- Note: Any closets or storage spaces, which the vent passes through must be enclosed.

#### **Offset Chart**


GS 6"(152mm) Nominal Diameter ID							
Offset		Pipe Len		Height			
inches	mm	inches mm		inches mm			
4 3⁄4	121	0	0	13 1/4	337		
9	229	6	152	17 1/2	445		
11 1/4	286	9	229	19 1/2	495		
13 1/4	337	12	305	21 3/4	552		
21 3/4	552	24	610	30 1/4	768		
30 1/4	768	36	914	39	991		
38	965	48	1219	47	1194		



### INSTALLATION PROCEDURES for FPI Direct Vent System (Flex)

- Locate the unit in the framing, rough in the gas (preferably on the right side of the unit) and the electrical (Junction block is on the left side) on the left. Locate the centerline of the termination and mark wall accordingly. Cut a 10"(254mm) hole in the wall (inside dimension).
- Note: A 2" clearance at the top and 1 1/2" clearance around the liner must be maintained except that only a 1" (25mm) clearance is needed at the termination end. We recommend framing a 10"(254mm) x 10"(254mm) (inside dimensions) hole to give structural rigidity for mounting the termination.


Note: To make the installation more aesthetically pleasing, we recommend framing out a square to mount the terminal to.



- Note: If installing termination on a <u>siding</u> <u>covered wall</u>, <u>furring strips must</u> <u>be used</u> to ensure that the termination is not recessed into the siding.
- **2)** Level the fireplace and fasten it to the framing using nails or screws through the nailing strips.
- 3) Assemble the vent assembly by applying Mill Pac to the 4"(100mm) inner collar of the termination and slipping the 4"(100mm) liner over it at least 1-3/8" (35mm). Fasten with the 3 screws (drilling pilot holes will make this easier). Apply Mill Pac or high temperature silicone to the 6-7/8"(175mm) flex pipe and slip it over the 6-7/8" outer collar of the vent terminal at least 1-3/8"(35mm) and fasten with the 3 screws.
- NOTE: Horizontal sections must be supported at intervals not exceeding 3 feet (0.9 meter). (Flame picture and performance will be affected by sags in the liner).

- 4) Separate the 2 halves of the wall thimble and securely fasten the one with the tabs to the outside wall making sure that the tabs are on top and bottom. Fasten the other thimble half to the inside wall. The thimble halves slip inside each other and can be adjusted for 2 x 4 or 2 x 6 walls. The liners must slip over the collars a minimum of 1-3/8".
- 5) Slip the assembled liner and termination assembly through the thimble making sure the termination cap faces up (there are markings on the cap that show which way is up). This will position the termination cap with proper down slope for draining water. Fasten the cap to the outer wall with the 4 supplied screws.
- 6) Pull the centre 4"(100mm) liner and outer 6-7/8"(175mm) liner out enough to slip over the flue collars of the fireplace. (You may wish to cut the liner shorter to make it more workable.) Do not bend liner more than 90°.
- 7) Apply Mill Pac over the fireplace inner collar and slip the 4"(100mm) liner down over it and attach with 3 supplied screws.
- 8) Do the same with the 6-7/8"(175mm) liner.
- Apply a bead of silicone between the thimble and termination and around the outer edge of the terminal at the wall in order to keep the water out.

**IMPORTANT:** Do not locate termination hood where excessive snow or ice buildup may occur. Be sure to check vent termination area after snow falls, and clear to prevent accidental blockage of venting system. When using snow blowers, make sure snow is not directed towards vent termination area.



#### P36-NG3 System Data

For 0 to 4500 feet altitude Burner Inlet Orifice Sizes: #37		
Max. Input Rating30,000 Btu/hMin. Input Rating15,300 Btu/h		
Output Capacity with blower Off		
22,600 Btu/h		
Output Capacity with blower On		
23,000 Btu/h		
Minimum Output with blower Off 11,500 Btu/h		
Supply Pressure min.5.0" w.c.		
Manifold Pressure (High) 3.8"+/- 0.2"w.c.		
Electrical: 120 V A.C. System.		

 Electrical: 120 V A.C. System.
 Circulation Fan: variable speed 130 CFM.
 Log Set: Ceramic fibre, 7 per set.
 Vent System: Simpson Dura-Vent Direct Vent System or FPI Direct Vent System (Flex)

#### P36-LP3 System Data

For 0 to 2000 feet altitude

Burner Inlet Orifice Sizes: #52

Max. Input Rating 30,000 Btu/h Min. Input Rating 15,000 Btu/h Output Capacity with blower Off 22,800 Btu/h Output Capacity with blower On 23,200 Btu/h Minimum Output with blower Off 11,700 Btu/h

For 2000 to 4500 feet altitude

Burner Inlet Orifice Sizes: #53 Max. Input Rating 25,000 Btu/h Min. Input Rating 12,600 Btu/h Output Capacity with blower Off 19,000 Btu/h Output Capacity with blower On 19,300 Btu/h Minimum Output with blower Off 11,700 Btu/h

For 0 to 4500 feet Altitude:

Supply Pressure min.12.0" w.c.

Manifold Pressure (High) 11"+/- 0.2" w.c.

Electrical: 120 V A.C. System. Circulation Fan: variable speed 130 CFM. Log Set: Ceramic fibre, 7 per set. Vent System: Simpson Dura-Vent Direct Vent System Note: Output capacity:

The efficiency rating of the appliance is a product thermal efficiency rating determined under continuous operating conditions and was determined independently of any installed system.

Vent height may or may not change your efficiency ratings.

### HIGH ELEVATION

This unit is approved in Canada for altitude 0 to 4500 ft. (CAN1 2.17-M91) with the orifice supplied.

# GAS LINE

The gas line is brought through the right of the appliance. The gas valve is situated on the right hand side of the unit and the gas inlet is on the right hand side of the valve.

The gas line connection may be made of rigid pipe, copper pipe or an approved flex connector. (If you are using rigid pipe, ensure that the valve can be removed for servicing.) Since some municipalities have additional local codes it is always best to consult with your local authorities and the CAN/CGA B149 installation code.

For USA installations follow local codes and/or the current National Fuel Gas Code, ANSI Z223.1.


When using copper or flex connectors use only approved fittings. Always provide a union so that gas lines can be easily disconnected for servicing. Flare nuts for copper lines and flex connectors are usually considered to meet this requirement.

Important: Always check for gas leaks with a soap and water solution or gas leak detector. Do not use open flame for leak testing.


## PILOT ADJUSTMENT

Periodically check the pilot flames. Correct flame pattern has three strong blue flames: 1 flowing around the thermopile, 1 around the thermocouple and 1 flowing across the burner (it does not have to be touching the burner).

Note: If you have an incorrect flame pattern, contact your FPI dealer for further instructions.



Incorrect flame pattern will have small, probably yellow flames, not coming into proper contact with the rear burner or thermopile or thermocouple.



## GAS PIPE PRESSURE TESTING

The appliance must be isolated from the gas supply piping system by closing its individual manual shut-off valve during any pressure testing of the gas supply piping system at test pressures equal to or less than 1/2 psig. (3.45 kPa). Disconnect piping from valve at pressures over 1/2 psig.


The manifold pressure is controlled by a regulator built into the gas control, and should be checked at the pressure test point.


- Note: To properly check gas pressure, both inlet and manifold pressures should be checked using the valve pressure ports on the valve.
- 1) Make sure the valve is in the "OFF" position.
- Loosen the "IN" and/or "OUT" pressure tap(s), turning counterclockwise with a 1/8" wide flat screwdriver.
- Attach manometer to "IN" and/or "OUT" pressure tap(s) using a 5/16" ID hose.

- Light the pilot and turn the valve to "ON" position.
- The pressure check should be carried out with the unit burning and the setting should be within the limits specified on the safety label.
- 6) When finished reading manometer, turn off the gas valve, disconnect the hose and tighten the screw (clockwise) with a 1/8" flat screwdriver. <u>Note: Screw should be</u> <u>snug, but do not over tighten.</u>

#### S.I.T. VALVE DESCRIPTION

- 1) Gas cock knob
- 2) Manual high/low adjustment
- 3) Pilot Adjustment
- 4) Thermocouple Connection option
- 5) Outlet Pressure Tap
- 6) Inlet Pressure Tap
- 7) Pilot Outlet
- 8) Main Gas Outlet
- 9) Alternative TC Connection Point





CONVERSION KIT FROM NATURAL GAS TO PROPANE MODEL #512-969 FOR P36-3 USING SIT 820 NOVA GAS VALVE

## THIS CONVERSION MUST BE DONE BY A QUALIFIED GAS FITTER IF IN DOUBT DO NOT DO THIS CONVERSION !!

#### Conversion Kit Contains:

Qt	y. Part #	Description
1	910-018	SIT Conversion Kit-50%
		Turndown LP
1	910-037	LP Injector (Pilot Orifice)
1	904-390	Burner Orifice #52
1	908-255	Decal "Converted to Propane'
1	908-528	Red "PROPANE" label
1	918-013	LP Conversion Decal (not
		required for P90)
1	908-529	5/32" Allen Key
1	908-793	Instruction Sheet

- 1) Shut off the gas supply
- 2) Remove the louvers (and bay door if it is installed).
- 3) Open the flush door and remove the door.
- 4) Remove the logs, embers, and brick panels (if used).
- 5) Remove the 2 screws holding the Burner Assembly to the firebox base. Push the Burner Assembly to the left and lift out.



Remove the 2 screws, push Burner Assembly to the left and lift out.

6) Pull off the pilot cap to expose the pilot orifice.



7) Unscrew the pilot orifice with the allen key and replace with the LP pilot orifice in the kit and replace pilot cap.




 Remove burner orifice with a 1/2" wrench and discard. Use another wrench to hold on to the elbow behind the orifice.



Burner Orifice

- Reinstall new burner orifice LP stamped #52 and tighten.
- Remove and discard the 3 pressure regulator mounting screws (A), pressure regulator tower (B) and diaphragm (C).
- 11) Insure that the rubber gasket (D) is properly positioned and install the new HI/LO pressure regulator assembly to the valve using the new screws (E) supplied with the kit. Tighten screws securely.
- 12) Reverse steps 5) to 2).
- 13) Attach clear label "This unit has been converted to Propane" near or on the serial # decal. Attach white label "This valve has been converted from NG to LPG using SIT conversion Kit Code 0.907.202" onto the valve.

- 14) Replace yellow "Natural Gas" label with red "Propane" label
- 15) Check for gas leaks.
- 16) Check inlet and outlet pressures.
- 17) Check operation of flame control.
- 18) Check for proper flame appearance and glow on logs.



## **OPTIONAL** BRICK PANELS

1) Undo the bottom 2 door latches and open and remove glass door. Remove logs.

#### Note: The logs must not be in the unit.


2) Insert the back brick panel first by carefully slipping it between the back wall of the firebox and the rear log bracket.




3) Put the side panels in next. Slide them in from the front and push them flat up against the wall. Be very careful not to scratch them on the firebox hardware.

> Leff Right Side Side Panel Panel

4) Install the 2 brick retaining clips, one on each side.





## LOG SET **INSTALLATION**

Read the instructions below carefully and refer to the diagrams. If logs are broken do not use the unit until they are replaced. Broken logs can interfere with the pilot operation.


The gas log kit (Part # 512-930) contains the following pieces:

a) 02-49 Rear Log Middle Left Log 02-55 b) C) 02-50 Front Left Log Center Left Log d) 02-53 02-51 Front Bottom Log e) Center Right Log f) 02-54 Middle Right Log g) 02-52 Embers h)



i)






The "02" refer numbers (i.e. 02-49) are molded into the rear of each log.

#### NOTE: If you will be installing the optional Brick Panels, install the Brick Panels prior to installing the logs.

- 1) Carefully remove the logs from the box and unwrap them. The logs are fragile, handle with care - do not force into position.
- 2) Sprinkle the vermiculite around the firebox base.




3) Place the Log 02-49 on the rear log support pins with the flat side to the back.

# INSTALLATION





4) Place Log <u>02-51</u> on the front right side of the burner. Push the back of the log against the 2 brackets with the notch on the bottom right side of the log fitting into the right side of the grate.




Cutouts

02-49

2nd Grate Tab

02-5:

Log 02-53.





Notch



Bracket





5) Position Log <u>02-53</u> across the cutouts in Logs 02-49 and 02-51 with the notch on the left side of the log fitting into the 2nd grate tab.

02-49 02-55 02-53 02-51

6) Place the bottom left front edge of Log

tray and rest the log on the cutout on

02-55 against the rear bracket on the burner

Rear Bracket

 Sit Log <u>02-50</u> on the front left side of the burner. Push the back of the log against the 2 front brackets with the notch on the bottom of the log fitting into the first grate tab. 8) Position Log <u>02-54</u> across the cutouts in Logs 02-51 and 02-53. The notch in the bottom right end fitting against the 5th grate tab.



5th Grate Tab

# INSTALLATION

 Place Log <u>02-52</u> between Logs 02-51 and 02-49 and on the indentation on Log 02-54. The bottom right end sits behind the rear grate tab.



Log indentation




Photo shows rear grate tab. Log 02-51 was removed to show the positioning of Log 02-52.

**10)** Place the embers on the front of the burner tray in the places shown on the photo.



Place embers in these 3 locations on the burner tray.



Embers

- 11) Test fire to ensure proper light off (make sure flame flows smoothly from one end of burner to the other). If there is any flame hesitation, check that area for any blockage of the burner ports.
- **12)** Install flush glass and bay glass (if used) as per instructions in this manual.

3-0


5



#### STANDARD FLUSH DOOR

**The standard flush door** comes with a black frame. To install the frame, simply hook the top door flange onto the top of the unit and swing the door towards the unit, see diagram 1.

Be careful that the glass gasket does not roll up; there must be a gap between the gasket and the door lip to ensure that the door sits securely on the unit, see Diagram 2.



#### Option 1: REMOTE CONTROL

Use the FPI Remote Control Kit approved for this unit. Use of other systems may void your warranty.

The remote control kit comes with a hand held transmitter, a receiver and a wall mounting plate.

- Choose a convenient location on the wall to install the receiver and the receptacle box (protection from extreme heat is very important). Run wires from the fireplace to that location. Use the Thermostat Wire Table.
- Connect the two wires to the gas valve. See diagram below.

#### CAUTION Do not connect millivolt remote control wires to 120V wire.

3) Install 3 AAA alkaline batteries in transmitter and 4 AA alkaline batteries in the receiver. Install the receiver and its cover in the wall. Switch the remote receiver to "remote" mode. The remote control is now ready for operation.

#### Option 2: WALL SWITCH

- Run the wire through the right or left side inlet opening. Be careful not to damage wire.
- Note: We recommend a maximum of 15' of wire but if you wish to go with a longer run, use the Thermostat Wire Table.
- Connect the wire to the wall switch and install into the receptacle box. See page 36 for wiring diagrams.

CAUTION Do not connect millivolt wall switch wire to 120V wire.

#### Option 3: WALL THERMOSTAT

A wall thermostat may be installed if desired, connect the wires as per the wiring diagram. Use the table below to determine the maximum wire length.


Note: Preferable if the thermostat is in stalled on an interior wall.

FPI offers an optional programmable thermostat but any 250-750 millivolt rated non-anticipator type thermostat that is CSA, ULC or UL approved may be used.



#### Thermostat Wire Table

Recommended Maximum Lead Length (Two-Wire) When Using Wall Thermostat (CP-2 System)		
Wire Size	Max. Length	
14 GA.	50 Ft.	
16 GA.	32 Ft.	
18 GA.	20 Ft.	
20 GA.	12 Ft.	
22 GA.	9 Ft.	




-,01

#### WIRING DIAGRAM

This heater does not require a 120V A.C. supply for operation. In case of a power failure, the burner switch and the optional remote control/ thermostat will continue to operate. However, a 120V A.C. power supply is needed for the fan/blower operation.


(Do not cut the ground terminal off under any circumstances.)

NOTE: Even if the fan is not purchased with the unit, it is still a good idea to bring power to the receptacle box (provided with the unit) in case the fan is installed at a later date.




Caution: Ensure that the wires do not touch any hot surfaces and are away from sharp edges.

CAUTION: Label all wires prior to disconnection when servicing controls. Wiring errors can cause improper and dangerous operation.







# **OPERATING INSTRUCTIONS**

the bracket clip on the underside of the

firebox. Check that no wire will touch the

7) Attach the Fan control box to the Burner

Use the clip & hook on the side of the

control boxes to join them together.

8) Secure the two boxes together with one

Secure the 2 boxes together with one screw.

9) Position the control box assembly on the

slot on the right side bracket.

bottom louver and mark the position of the

hot surfaces. Diagram 2.

ON/OFF control box.

screw

#### **INSTALLING THE OPTIONAL FAN**

120 Volt AC power is needed for the fan switch and blower. The fan can be hard wired if desired. The receptacle box should be installed on the left hand side of the unit by a qualified electrician. The neutral (wider) slot of the polarized receptacle should be at the top.

Unit must be grounded at all times. Do not cut the ground terminal off under any circumstances.

- 1) Shut the power off.
- 2) Remove the standard flush door and the optional bay door, if installed. Open the bottom louver door.
- 3) Loosen the 2 screws holding the Burner ON/OFF switch and bracket to the bottom louver and lift the assembly out.
- 4) Turn the fan base on its side (with the base facing towards you) and then slide the fan in towards the rear of the unit. Turn the fan upright and slip it over the two mounting studs. Take care not to damage the insulation on the fan base. Ensure that the fan blades do not rub against the valve tubing. Diagram 1.

#### Electrical

Receptacle Hold control box assembly in place and mark the position of the right side slot 10) Remove the control box Push Fan down assembly and push the hold-down clip onto the louon mounting pins ver. Bend the tab until it is at 90° to the louver. G Ground Lug Plug fan power cord Diagram 1 into rear receptacle. Connect fan ground cable to ground lug. 11) Attach the two control boxes to the bottom Refer to wiring diagram. louver and tighten the 2 screws on the left side and 1 screw on the right side. 6) Slide the thermodisc/cover assembly into Thermodisc Bracket Thermodisc/Cover Secure left Assembly side with 2 screws. Diagram 2

Secure right side with one screw.

- 12) Secure the fan wires and power cord by attaching one of the adhesive backed wire holder clips (Part #910-199) onto the stove base. Use the second clip to bundle up the wires approximately 4" from the control box. Ensure that there is no interference with the wires when the louver is closed and that no wire will touch the hot metal surfaces or sharp edges.
- 13) Plug the fan power cord into the rear end of the receptacle box to provide the maximum clearance from the louvers.

#### **TO REMOVE THE FAN**

- 1) Shut the power off.
- 2) Reverse the above instructions.

Note: The bearings are lubricated for life. Do not lubricate them. Make sure you vacuum the fan area on a regular basis.

#### **IMPORTANT:**

These fans collect a lot of dust from within your home. Ensure you maintain these fan motors on a regular basis by vacuuming out the fan blades and housing using a soft brush nozzle.

#### **OPERATING** INSTRUCTIONS

- 1) Read and understand these instructions before operating this appliance.
- 2) Check to see that all wiring is correct and enclosed to prevent possible shock.
- 3) Check to ensure there are no gas leaks.
- 4) Make sure the glass in the door frame is properly positioned. Never operate the appliance with the glass removed.
- 5) Verify that the venting and cap are unobstructed.
- 6) Ensure that the brick panels are installed.
- 7) Verify log placement. If the pilot cannot be seen when lighting the unit, the logs have been incorrectly positioned.
- 8) The unit should never be turned off, and on again without a Gas In

minimum of a Inlet Pressure 60 ✓Tap second - Outlet wait. Pressure Тар Shut Off Hi/Lo Pilot Adjustment

FPI P36-3 Zero Clearance Direct Vent Gas Fireplace

# **OPERATING INSTRUCTIONS**

#### LIGHTING PROCEDURE

IMPORTANT To ignite or reignite the pilot, you must first release the tension springs below the door.

Only when the pilot holds, without pressure being applied to the control knob, reapply the tension springs to the door. The unit **must not** be operated with the tension springs unattached.

#### IMPORTANT Gas cock knob cannot be turned from "PILOT" to "OFF" unless it is partially depressed.

- 1) Turn burner OFF using "ON/OFF" switch.
- Turn gas control knob so indicator points to "OFF" position and allow 5 minutes for any gas in the combustion chamber to escape.
- 3) Turn gas control knob counterclockwise so indicator points to the "PILOT" position. Depress the gas control knob fully. Depress the igniter button several times until the pilot lights. After approximately one minute, release the gas control knob. The pilot flame should continue to burn. If the pilot does not remain lit, repeat operation allowing a longer period before releasing gas control knob.
- When the pilot stays lit, turn the gas knob further counterclockwise to the "ON" position.
- 5) Use the wall switch, thermostat or remote control to turn on the unit.
- 6) Rotate the flame height regulator to adjust the flame height higher or lower.

### SHUTDOWN PROCEDURE

- 1) Use the wall switch, thermostat or remote control to turn off the main burner.
- 2) Turn the main gas control clockwise to the "OFF" position to turn off the pilot.
- Turn off all electric power to appliance if service is to be performed.

#### **FIRST FIRE**

The first fire in your stove is part of the paint curing process. To ensure that the paint is properly cured, it is recommended that you burn your fireplace for at least four (4) hours the first time you use it with the fan on.

When first operated, the unit will release an odour caused by the curing of the paint, the burning off of any oils remaining from manufacturing. Smoke detectors in the house may go off at this time. Open a few windows to ventilate the room for a couple of hours.

The glass panel may require cleaning after the unit has cooled down.

# DO NOT ATTEMPT TO CLEAN THE GLASS WHILE IT IS HOT.

Note: When the glass is cold and the appliance is lit, it may cause condensation and fog the glass. This condensation is normal and will disappear in a few minutes as the glass heats up.

#### DO NOT BURN THE APPLIANCE WITHOUT THE GLASS FRONT IN PLACE.

During the first few fires, a white film may develop on the glass front as part of the curing process. The <u>glass should</u> <u>be cleaned</u> or the film will bake on and become very difficult to remove. Use a non-abrasive cleaner and NEVER clean the glass while it is hot.


#### AERATION ADJUSTMENT

The air shutter can be adjusted by moving the adjusting wire up or down. The wire is accessed through the bottom louver opening. Open the air shutter for a blue flame or close for a yellower flame. The burner aeration is factory set but may need adjusting due to either the local gas supply or altitude.

Minimum Air Shutter Opening: 3/16" Natural Gas 1/2" Propane

**CAUTION:** Carbon will be produced if air shutter is closed too much.

- Note: Any damage due to carboning resulting from improperly setting the aeration controls is NOT covered under warranty.
- Note: Aeration Adjustment should only be performed by an authorized FPI Installer at the time of installation or service.



Adjustment wire: Push to close or pull to open aeration cap. Closed - Tall yellow Open - Short Blue

# NORMAL OPERATING SOUNDS OF GAS APPLIANCES

It is possible that you will hear some sounds from your gas appliance. This is perfectly normal due to the fact that there are various gauges and types of steel used within your appliance. Listed below are some examples. All are **normal operating sounds** and should not be considered as defects in your appliance.

#### Blower:

FPI gas appliances use high tech blowers to push heated air farther into the room. It is not unusual for the fan to make a "whirring" sound when ON. This sound will increase or decrease in volume depending on the speed setting of your fan speed control.

#### Burner Tray:

The burner tray is positioned directly under the burner tube(s) and logs and is made of a different gauge material from the rest of the firebox and body. Therefore, the varying thicknesses of steel will expand and contract at slightly different rates which can cause "ticking" and "cracking" sounds. You should also be aware that as there are temperature changes within the unit these sounds will likely re-occur. Again, this is normal for steel fireboxes.

#### Blower Thermodisc:

When this thermally activated switch turns ON it will create a small "clicking" sound. This is the switch contacts closing and is normal.

#### **Pilot Flame:**

While the pilot flame is on it can make a very slight "whisper" sound.


#### Gas Control Valve:

As the gas control valve turns ON and OFF, a dull clicking sound may be audible, this is normal operation of a gas regulator or valve.

#### Unit Body/Firebox:

Different types and thicknesses of steel will expand and contract at different rates resulting in some "cracking" and "ticking" sounds will be heard throughout the cycling process.

#### COPY OF THE LIGHTING PLATE INSTRUCTIONS



- 1) Always turn off the gas valve before cleaning. For relighting, refer to lighting instructions. Keep the burner and control compartment clean by brushing and vacuuming at least once a year. When cleaning the logs, use a soft clean paint brush as the logs are fragile and easily damaged.
- 2) Clean appliance and door with a damp cloth (never when unit is hot). Never use an abrasive cleaner. The glass should be cleaned with a gas fireplace glass cleaner. The glass should be cleaned when it starts looking cloudy.
- 3) The heater is finished in a heat resistant paint and should only be refinished with heat resistant paint. FPI uses StoveBright Paint - Metallic Black #6309.
- Make a periodic check of burner for proper position and condition. Visually check the flame of the burner periodically, making sure the flames are steady; not lifting or floating. If there is a problem, call a qualified
- 5) The appliance and venting system must be inspected before use, and at least annually, by a qualified field service person, to ensure that the flow of combustion and ventilation air is not obstructed.

#### Note: Never operate the appliance without the glass properly secured in

- 6) Do not use this appliance if any part has been under water. Immediately call a qualified service technician to inspect the appliance and to replace nay part of the control system and any gas control which has been under water.
- 7) Verify operation after servicing.

#### **General Vent Maintenance**

Conduct an inspection of the venting system semi-annually. Recommended areas to inspect

- 1) Check the Venting System for corrosion in areas that are exposed to the elements. These will appear as rust spots or streaks, and in extreme cases, holes. These components should be replaced immediately.
- 2) Remove the Cap, and shine a flashlight down the Vent. Remove any bird nests, or other foreign material.
- 3) Check for evidences of excessive condensation, such as water droplets forming

in the inner liner, and subsequently dripping out the joints, Continuous condensation can cause corrosion of caps, pipe, and fittings. It may be caused by having excessive lateral runs, too many elbows, and exterior portions of the system being exposed to cold weather.

4) Inspect joints, to verify that no pipe sections or fittings have been disturbed, and consequently loosened. Also check mechanical supports such as Wall Straps, or plumbers' tape for rigidity.

### GOLD-PLATED or BRASS LOUVERS

The 24 carat gold-plated or brass finish on the louvers and trim requires little maintenance, and need only be cleaned with a damp cloth. DO NOT use abrasive materials or chemical cleaners, as they may harm the finish and void the warranty. **Clean any fingerprints off before turning the unit on.** 

#### GOLD-PLATED or BRASS TRIM

The 24 carat gold plated or brass finish on the trim requires little maintenance, and need only be cleaned with a damp cloth. DO NOT use abrasive materials or chemical cleaners, as they may harm the finish and void the warranty. Clean any fingerprints off before turning the unit on. If the top louvers start to discolour, check the door gasket seal and replace if necessary.

# LOG REPLACEMENT

The unit should never be used with broken logs. Turn off the gas valve and allow the unit to cool before opening door and carefully remove the logs. (The pilot light generates enough heat to burn someone.) If for any reason a log should need replacement, you must use the proper replacement log. The position of these logs must be as shown in the diagrams under Log Installation.

Note: Improper positioning of logs may create carbon build-up and will severely alter the unit's performance which is not covered under warranty.

#### THERMOPILE/ THERMOCOUPLE

- 1) Open the bottom louvers.
- 2) Loosen the thermocouple or thermopile with a 7/16" wrench.
- Disconnect thermocouple by loosening nut from the valve with a 9mm wrench. Disconnect thermopile by loosening 2 screws marked TP on the valve.
- 4) Drop the thermocouple or thermopile down from the bracket and pull it out of the unit.
- 5) Reinstall the new ones in reverse order.

# **GLASS GASKET**

If the glass gasket requires replacement use 5/8" flat glass gasket for the Bay Front (Part # 936-243) and a tadpole glass gasket for the Flush Front (Part # 936-155).

# DOOR GLASS

Your FPI fireplace is supplied with high temperature, 5 mm Neoceram ceramic glass that will withstand the highest heat that your unit will produce. If your glass requires cleaning, we recommend using an approved glass cleaner available at all authorized dealers. Do not use abrasive materials. Do not clean the glass when hot.


In the event that you break your glass by impact, purchase your replacement from an authorized FPI dealer only, and follow our step-by-step instructions for replacement.

WARNING: Do not operate the appliance with the glass panels removed, cracked or broken. Replacement of the glass panels should be done by a licensed or qualified service person.

#### CAUTION: Wear gloves when removing damaged or broken glass.


#### **Flush Glass Replacement**

Remove the flush door front, see page 36. Remove the 4 glass clips from each corner. Slide in the new replacement glass. Push the 4 glass clips back onto the frame. **The glass must have gasketing around it.** 



#### **Bay Glass Replacement**

- 1) Remove the door from the unit and place on a soft surface to prevent scratching.
- 2) Remove the nuts holding the glass clips in place and remove.
- 3) Replace the glass. The glass must have gasketing around it.
- Reverse the previous steps, replace the glass clips and fasten with the nuts but do not over tighten, as this can break the glass.
- 6) Replace door on the stove and check the seal.



# MAINTENANCE

#### **REMOVING VALVE**

- 1) Shut off the gas supply.
- 2) Remove the louvers (and bay door if it is on).
- 3) Open the flush door and remove the door.
- 4) Remove the logs.
- 5) Remove the burner/grate assembly by removing the two Phillips head screws and then lift the burner assembly out.






Diagram 1: Remove the left and right screws and then lift out the burner/grate assembly.

Remove the rear log stand by removing the 2 screws.




Diagram 2: Rear Log Stand and Valve Tray Assembly

- Disconnect the inlet gas line. See diagram 2.
- Disconnect the 2 TP wires and the 2 TH wires from the valve.
- 9) Remove the 10 Phillips head screws securing the valve tray assembly in place (diagram 2) and then lift the entire assembly out (diagram 3).

- 10) Undo the pilot tube from the valve with a 7/ 16" wrench.
- 11) Undo the quick drop out thermocouple nut on the valve with a 9mm (metric) wrench.
- **12)** Remove the Piezo igniter wire and push button assembly.
- 13) Undo the "gas out" flare nut with a 13/16" wrench.
- 14) Undo the "gas out" flare fitting with an 11/ 16" wrench.
- **15)** Remove the 4 Phillips head screws from the sides of the valve bracket and remove valve.





Hint: If you are using black pipe, ensure that there is a union by the valve, otherwise removal will be almost impossible.

# INSTALLING VALVE

- 1) Attach the valve to the valve bracket with the 4 (m5x8 metric) screws provided.
- 2) Reconnect the "gas out" flare fitting with an 11/16" wrench.
- Reconnect the "gas out" flare nut with a 13/ 16" wrench.
- Install piezo ignitor push button assembly and reconnect wire.
- 5) Reconnect the quick drop out thermocouple nut with a 9mm wrench.
- 6) Reconnect the pilot tube nut with a 7/16" wrench.
- Scrape off the old gasket from the floor of the firebox and from the valve tray assembly.
- Install a new gasket and reinstall the valve tray assembly.

#### Note: Failure to install a new gasket may severely affect the appliance performance.

- 9) Reinstall the 10 hold down screws.
- **10)** Hook up the 2 TP and 2 TH wires to the appropriate connections on the valve.
- 11) Reinstall the front log stand.
- 12) Install Burner/grate assembly
- 13) Hook up the gas line and check for gas leaks with a soap and water solution or a gas leak detector. (Do not use open flame for leak testing.)
- 14) Fire up the unit temporarily
- 15) Check the manifold pressure.
- 16) Reinstall the logs and brick panels as needed.
- 17) Close the door and replace the louvers.
- **18)** Fire up the unit again and check for proper flame appearance and glow on logs.



# FLUSH & BAY DOOR OPTIONS




#### FLUSH TRIM


Attach the round magnets to the back of the top trim piece and to the bottom trim piece, then attach trim to the top and bottom of flush door.

#### **FLUSH LOUVERS**

- Install the top louver by sliding the two bracket clips into the brackets located underneath the top of the firebox.
- 2) The bottom louver has a hinge that is attached (2 screws per hinge) to the lip on bottom of the unit.
- DOUBLE SCREEN DOOR
- 1) Pull out the top louver.
- 2) Center the screen door and hook over the flush door.



-02



3) Open the bottom louver. Pull the Burner ON/ OFF control box from inside the bottom of the fireplace and position the slots in the bracket over the 2 screws on the left side of the bottom louver. Push down to lock into place. Tighten the screws.



Screws on louver bracket

Burner ON/OFF control box



Open the screen door(s) and secure the screen door to the flush door front with 2 clips on the bottom left and right side.



Clip locations




Clip installed on right side.

#### **BAY DOOR**

# The Bay louvers <u>MUST</u> be used with the Bay door option.

The optional Bay door is an overlay on the flush front. The standard flush door and glass must remain on the unit.


- Hook the top of the bay door over the flush door flange and swing the bottom against the bottom flange of the flush door.
- 2) Secure to the flush door bottom bracket with 2 screws provided.



# Slide the valve extension knobs onto the valve knobs.

#### **BAY TRIM**

Attach 4 supplied magnets each to the back of the top and bottom trim pieces, and attach trim to the top and bottom of Bay door.  Install bottom louver by sliding the two bracket clips into the brackets located underneath the bay door. Secure with 1 screw into each Bottom Louver Mounting Bracket as per diagram below. Use the bottom hole in the bracket.



Note: If any maintenance etc. must be done in the firebox, first remove the Bay louvers and door.

Shut Off

Ext. Knob

Bottom Louver

Louver

Bracket

HI/Lo

Ext. Knob

#### **FINISHING TRIM**

NOTE: Remove both the Flush Louvers or Bay Louvers and the Flush Front or Bay Front prior to installing the Finishing Trim. 1) Install the Finishing Trim sides as shown in the diagram, line up the holes in the side trim with the holes in the firebox side. 2) Secure with 2 screws per side. 3) Loosen the 3 screws in the top inside edge of the firebox. 4) Slide the Finishing Trim Top over the Side Trim pieces and fit the bottom bracket slots over the screws. Tighten the 3 screws to secure. 5) Loosen the 2 screws on the hinge bracket on both the left and right side of the louver. 6) Hook the bottom finishing trim to the side trims and snap in. 7) Tighten the 2 screws on the left and right hinge bracket to secure. Finishing Trim Top Finishing Trim Side Hinge Bracket -,01 Finishing Trim Bottom Hinge Bracket


# FULL SCREEN FRONT INSTALLATION

 Before beginning the installation, remove the Screen Doors from the Full Screen Door Frame by fully opening the doors and lifting up off of the hinges. See important note in step 7.


#### 2) Full Screen Door Frame Installation


a) Before attaching the Full Screen Door Frame to the unit, loosen the 3x#8 Philips Head Screws located on the inside top of the outer frame of the appliance. And remove the center screw.

Also loosen the #8 Philips Head Screw on the inner side of each hinge bracket as shown below.



b) Slide the cut-outs in the Top and Bottom Flange of the Full Screen Door Frame under the screw heads which were loosened in step 2a. Once the Frame is in place, tighten screws to secure.






**NOTE:** Should the finished wall protrude beyond the face of the unit, you can accommodate up to 1/2" depth.


Simply push in the Full Screen Door Frame until it aligns against the finished wall. Secure Top Flange of Full Screen Door Frame as described in step 2.

For the Bottom Flange of the Full Screen Door Frame, push the bottom of the Frame until it aligns with the wall. Use the inner cut-outs to secure the base of the Frame using the 2 x Hex Head Drill Point Screws provided.



Backside of Full Screen Door Frame Shown

- Install the hinges to the hinge brackets on the left and right side of the bottom of the outer frame, secure using 2 x #8 Philips Head Screws per hinge.
- 6) Slide the Top Grill into the louver brackets located on the inside top of the firebox. Push in place.




### ARCH SCREEN DOOR

#### Framing & Finishing

3) Install On/Off switch.

A non-combustible material 12" (305mm) above the Arch and 6" (153mm) on each side must be used. The Arch Screen Front also requires steel stud framing above and on each side of the unit (refer to

Diagram 1).



Note: The facing material has to go on after the unit is set.

1) Remove Glass Door. Refer to P36 Manual.

2) Remove 2 screws and bracket as indicated.







Diagram 2



4) Place bracket under the Flange. Secure with 2 screws as indicated in Diagram 4.




5) Loosen the 3 x #8 Phillips Head Screws located on the inside top of the outer frame of the appliance.



#### 6) Install Top Support Frame

#### Slide in the Top Support Frame using the slots as a guide. Secure and re-tighten the screws to the unit.


a) View of backside of Top Support Frame.




#### 8) Attach Top and Side Support Frame

a) Ensure the Side Supports are aligned with the corresponding hole on the Top Support Frame, then secure with 1 screw.

b) Repeat step on the other side.



b)




**Note:** The Nailing Strips can be adjusted, depending on the facing material (as indicated in Diagram 2).

#### 7) Side Support Frame

a) Mount Side Support Frame to unit as shown in diagram, then secure with 2 screws on each side.

b) Repeat step on the other side.






Diagram 2

#### 9) Optional

Install Optional 3-Panel Arch Door. (Refer to Install 3-Panel Arch Door Instruction Sheet).

10) **Change in Logo** Replace existing logo with Regency logo.



#### HAMPTON CAST FACEPLATE

- 1) Remove top louver.
- 2) Open bottom louver.
- 3) Install the left side faceplate by pushing in at the side of the firebox and line up with top and bottom holes on side. Secure with screws, tighten loosely.
- Slide top piece of faceplate into side faceplates by fitting mounting plates into brackets.

(Back View)



# **HAMPTON OPTIONS**

#### HAMPTON CAST GRILLS

1) Remove the 3 faceplate mounting phillips head screws from the inside top of firebox, and discard if necessary.



2) Place top grill in brackets located inside top of firebox as shown.





 Remove hinge brackets on bottom left and right side of firebox by removing 2 screws and discard brackets only.



Hinge bracket. Left side shown.

Install new hinge brackets using the same 2 screws removed in step 3



New hinge bracket. Left side shown. 5) Install hinge to bracket then secure with screw.



- 6) Place something underneath bottom grill to prevent scratching.
- 7) Line up hinge holes in bottom grill holes.
- 8) Place screws half way in -- do not secure completely.



 Place bracket over screws then push to the side against faceplate to lock in place as per diagram.



**10)** Tighten screws. (Screws will easily be tightened if using a stubby screwdriver.)

Black Metallic Grills Only: Mount grill stopper to bottom of firebox securing with one screw.



11) Adjust ball plunger if necessary.





The Balmoral Front

# PALACE SERIES OPTIONS


#### THE KENSINGTON FRONT INSTALLATION

1) Bend tabs downwards located at the back of the Kensington Front.




Backside of front shown.

 Secure the bottom frame of the Front by loosening the inner screw on the hinge brackets on both the left and right side of the firebox. Slide frame in place and secure.




3) Slide tabs into louver brackets located on the inside top of the firebox.






 Remove existing control switch box from under firebox by disconnecting wires connected to the valve at TH-TH/TP terminals and discard.



5) Connect the ON/OFF switch wires coming from the left side of the Front to the valve, with black hooked up to the TH/TP terminal and red hooked up to the TH terminal.

**NOTE:** If fan option is not used please see step (5) of optional fan installation for placement of fan control box.




- 6) For optional fan installation, see page 58.
- 7) For 2-panel & 3-panel door installation, see page 59.

Tabs

#### THE WESTMINSTER FRONT INSTALLATION

1) Install the hood to the Westminster Front by sliding the 4 cut-outs thru the screws and tighten to secure.



Westminster Front

Cut-out in Hood


2) Bend tabs located at the back of the Westminster Front upwards 90 degrees.



Bend tab upwards 90 degrees.

Backside of front shown.

 Secure the bottom frame of the Front by loosening the inner screw on the hinge brackets on both the left and right side of the firebox. Slide frame in place and secure.




4) Slide tabs into louver brackets located on the inside top of the firebox.



Bracket inside top of firebox.



 Remove existing control switch box from under firebox by disconnecting wires connected to the valve at TH-TH/TP terminals and discard.




Control Box

Wires connected to Valve.

6) Connect the ON/OFF switch wires coming from the left side of the Front to the valve, with black hooked up to the TH/TP terminal and red hooked up to the TH terminal.

**NOTE:** If fan option is not used please see step (5) of optional fan installation for placement of fan control box.



**7)** For optional fan installation, see page 63.

8) For 2-panel & 3-panel door installation, see page 64-65.

# PALACE SERIES OPTIONS

#### THE BALMORAL FRONT INSTALLATION


1) Bend tabs located at the back of the Balmoral Front upwards 90 degrees.



Bend tab upwards 90 degrees.

Backside of Front shown.

 Secure the bottom frame of the Front by loosening the inner screw on the hinge brackets on both the left and right side of the firebox. Slide frame in place and secure.




3) Slide tabs into louver brackets located on the inside top of the firebox.



-	-	-	10.00	-	
				1	


Bracket inside top of firebox.

 Remove existing control switch box from under firebox by disconnecting wires connected to the valve at TH-TH/TP terminals and discard.



5) Connect the ON/OFF switch wires coming from the left side of the Front to the valve, with black hooked up to the TH/TP terminal and red hooked up to the TH terminal.

**NOTE:** If fan option is not used please see step (5) of optional fan installation for placement of fan control box.



- 6) For optional fan installation, see page 63.
- 7) For 2-panel & 3-panel door installation, see page 64-65.

#### THE KENSINGTON, WESTMINSTER & BALMORAL FRONT OPTIONAL FAN INSTALLATION

1) Remove fan cover by undoing screw.



- 2) Disconnect fan switch wires and discard fan cover with wires.
  - Discard Fan
     Disconnect

     Cover with Wires
     Disconnect
- 3) Connect new fan control box wires to the existing fan plug wires (red to red, black to black).




New Fan Control Box

4) Tuck wires in new fan control box and secure with screw.



5) Place fan control box under left side of firebox and secure to left side vertical hinge bracket supplied screw.



Vertical Hinge Bracket

Fan Control Box

#### THE KENSINGTON & BALMORAL FRONT 2-PANEL DOOR INSTALLATION

1) Install sub-frame by hooking top over glass door, push in bottom of frame and secure with 2 screws.



Sub-Frame

Secure bottom of sub-frame with screws.



2) Mount 2-panel door frame to flange on sub-frame, ensuring to line up holes. Secure using the 6 screws provided.




 Hook left side door to door frame by placing the door hinges (top & bottom) over pins on door frame. Repeat for right side door.

**Note:** It will be easier to put the door in place by starting with the bottom hinge.



**Note:** If you find that the left or right side door is lower then the other, use the spacer provided to help align the doors.

The spacer is to be placed over the bottom pin before installing the screen door.



Spacer

#### THE KENSINGTON, WESTMINSTER & BALMORAL FRONT 3-PANEL DOOR INSTALLATION

1) Install sub-frame by hooking top over glass door, push in bottom of frame and secure with 2 screws.



Secure bottom of sub-frame with screws.

Car




2) Mount 3-panel door frame to flange on sub-frame, ensuring to lineup holes. Secure using the 4 screws provided.



# REPLACEMENT PARTS LIST

#### MAIN ASSEMBLY




# PARTS LIST

#### **BURNER ASSEMBLY & LOG SET**


	Part #	Description			
	513-574/P	Valve Assy - Natural Gas			
	513-576/P	Valve Assy - Propane		95	
52)		Valve Tray - NG/LP		85	
	430-055	Gasket - Valve Access			UGD
/		Plate			The stand of the s
54)	910-421	Pilot ON/OFF 3" Extension			400
,		Knob		1111	
55)	910-422	HI/LOW 3" Extension Knob		ALL REAL	E HU
	910-190	Piezo Ignitor			
	910-378	SIT Valve - Natural Gas		(SB)	
	910-380	SIT Valve - Propane			Was and a second s
58)	*	Valve Bracket			A A A A A A A A A A A A A A A A A A A
59)	*	Firebox Base	(		A A A A A A A A A A A A A A A A A A A
66)	910-038	Pilot Assy - S.I.T	66		
		3 Flame NG			
	910-039	Pilot Assy - S.I.T		83	
07)	*	3 Flame LP			
67)		Pilot Holder		84	
68)	W840470 904-240	Pilot Assembly Gasket		.82	
		Orifice #37 - Natural Gas		02	
	904-390 936-170	Orifice #52 - Propane Orifice Gasket	68		84
	910-036	Pilot Orifice NG			
	910-037	Pilot Orifice LP			
	010 001		00		
79)	512-525	Burner Assy	8565		
	511-030	Burner Grate Assy			is.
	430-101	Rear Log Support Bracket	67		79
84)		Deflector			
85)	512-930	Log Set			
*N.		non lo como contino ent			
NU	avaliable as a	replacement part.			
			68	52	>
				J2	
				53	· · · · · · · · · · · · · · · · · · ·
			59		
	(				
					No the second se
				58	
				and a	
				56	
				, Se	
					E7
				and the second sec	57
				54	55

#### **REGENCY FLUSH FRONT ACCESSORIES**




PARTS LIST

#### **REGENCY BAY FRONT ASSEMBLY**



# PARTS LIST

#### HAMPTON CAST FACEPLATE & GRILL ASSEMBLY



# NOTES

				(
				3
			- Chi	
		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		
	<u> </u>			
	2011			
1	<i>,</i>			
0				

# NOTES

				- B
				03
			0	6
			610	
		<u> </u>		
		•		
	Gor			
2	13			

# NOTES

$\frac{3^{43}}{5^{43}}$	
$\frac{3^{3}}{5^{3}}$	
$\frac{3}{6}$	
$\frac{623}{60}$	
	6
	G
	<u>0</u> <sup>V</sup>



FPI Fireplace Products are designed with reliability and simplicity in mind. In addition, our internal Quality Assurance Team carefully inspects each unit thoroughly before it leaves our facility. FPI Fireplace Products International Ltd. is pleased to extend this limited lifetime warranty to the <u>original purchaser</u> of a FPI Product. This warranty is not transferable.

#### The Warranty: Limited Lifetime

The combustion chamber, heat exchanger, burner tubes/pans, logs, brick panels and gold plating (against defective manufacture only) are covered under the Limited Lifetime Warranty for five (5) years for parts and subsidized labour\* and parts only thereafter.

Glass is covered for lifetime against thermal breakage only, parts and subsidized labour\* for five (5) years and parts only thereafter from date of purchase

External casting, surrounds and grills are covered against cracks and warps resulting from manufacturer defects, parts and subsidized labour\* for three (3) years from the date of purchase and parts only thereafter.

Special Finishes - One year on brushed nickel and antique copper full screens and doors. You can expect some changes in color as the product "ages" with constant heating and cooling. FPI warranties the product for any manufacturing defects on the original product. However, the manufacturers warranty does not cover changing colors and marks, ie. finger prints, etc applied after the purchase of the product. Damage from the use of abrasive cleaners is not covered by warranty.

Electrical and mechanical components such as blowers, switches, wiring, thermodiscs, FPI remote controls, spill switches, thermopiles, thermocouples, pilot assembly components, and gas valves are covered for one year parts and subsidized labour\* from the date of purchase. Blowers and valves replaced under warranty are considered repairs and continue as if new with appliance. ie. twelve (12) months from original purchase date of appliance with a minimum of three (3) months coverage from date of replacement.

FPI venting components are covered parts and subsidized labour\* for three (3) years from date of purchase.

Simpson Dura-Vent venting components (Direct Vent units) are covered by Simpson Dura-Vent Inc. warranty.

#### Conditions:

Any part or parts of this unit which in our judgement show evidence of such defects will be repaired or replaced at FPI's option, through an accredited distributor or agent provided that the defective part be returned to the distributor or agent <u>Transportation Prepaid</u>, if requested.

Porcelain/Enamel - Absolute perfection is either guaranteed nor commercially possible. Any chips must be reported and inspected by an authorized dealer within three days of installation. Reported damage after this time will be subject to rejection.

It is the general practice of FPI to charge for larger, higher priced replacement parts and issue credit once the replaced component has been returned to FPI and evaluated for manufacturer defect.

The authorized selling dealer is responsible for all in-field service work carried out on your FPI product. FPI will not be liable for results or costs of workmanship from unauthorized service persons or dealers.

At all times FPI reserves the right to inspect product in the field which is claimed to be defective.

All claims must be submitted to FPI by authorized selling dealers. It is essential that all submitted claims provide all of the necessary information including customer name, purchase date, serial #, type of unit, problem, and part or parts requested, without this information the warranty will be invalid.

#### Exclusions:

This limited Lifetime Warranty does not extend to or include paint, door or glass gasketing or trim.

At no time will FPI be liable for any consequential damages which exceed the purchase price of the unit. FPI has no obligation to enhance or modify any unit once manufactured. ie. as products evolve, field modifications or upgrades will not be performed.

FPI will not be liable for travel costs for service work.

Installation and environmental problems are not the responsibility of the manufacturer and therefore are not covered under the terms of this warranty policy.

Embers, rockwool, gaskets, door handles and paint are not covered under the terms of this warranty policy.

Any unit which shows signs of neglect or misuse is not covered under the terms of this warranty policy.

The warranty will not extend to any part which has been tampered with or altered in any way, or in our judgment has been subject to misuse, improper installation, negligence or accident, spillage or downdrafts caused by environmental or geographical conditions, inadequate ventilation, excessive offsets, negative air pressure caused by mechanical systems such as furnaces, fans, clothes dryer, etc.

Freight damage to stoves and replacement parts is not covered by warranty and is subject to a claim against the freight carrier by the dealer.

FPI will not be liable for acts of God, or acts of terrorism, which cause malfunction of the appliance.

Performance problems due to operator error will not be covered by this warranty policy.

Products made or provided by other manufacturers and used in conjunction with the operation of this appliance without prior authorization from FPI, may nullify your warranty on this product.

Any alteration to the unit which causes sooting or carboning that results in damage to the interior / exterior facia is not the responsibility of FPI.

\* Subsidy according to job scale as predetermined by FPI.

FPI fireplaces are designed with reliability and simplicity in mind. In addition, our internal Quality Assurance Team carefully inspects each unit thoroughly before it leaves our door.

FPI Fireplace Products International Ltd. is pleased to extend this Limited Lifetime Warranty to the original purchaser of a FPI Product.

See the inside back cover for details.

Register your Regency online at http://www.regency-fire.com

Register your Hampton online at http://www.hampton-fire.com

Register your Palace online at http://www.palace-fire.com

Installer: Please complete the following information

Dealer Nar	ne & A	ddress:_
------------	--------	----------

Installer:

Phone #:

Date Installed:

Serial No.:

FPI, Regency, Hampton and The Palace Series are trademarks of FPI Fireplace Products International Ltd. © Copyright 2005, FPI Fireplace Products International Ltd. All rights reserved.